



ONCE THE EXISTING FLOOR COVERING HAS BEEN REMOVED, WIRE BRUSH BEAMS FOR INSPECTION BY A STRUCTURAL ENGINEER PRIOR TO PAINTING. ALL STEELWORK IS TO BE PAINTED TO ACHIEVE A LIFE TO FIRST MAINTENANCE OF 20 YEARS. DETAILS OF THE PROPOSED PROTECTION SYSTEM IS TO BE COMPATIBLE WITH FIRE PROTECTION SYSTEM. APPLY PROTECTIVE ZINC RICH COATING TO THE STEEL BEAMS. ALL STEELWORK IS THEN TO RECEIVE 2No. COATS OF BITUMINOUS PAINT 150 MICRONS DRY FILM THICKNESS.

**NOTE:**  
5.0KN/M² IMPOSED FLOOR LOAD

project  
CRANLEIGH VILLAGE HALL,  
VILLAGE WAY,  
CRANLEIGH,  
GU6 8AF

drawing title  
**PROPOSED STAGE FLOOR**

© COPYRIGHT

rev	description		date
Drawn TW	Scale 1:50		
Date April 2024	Scale As stated at A3		
Job No <b>21995</b>	Drg No <b>101</b>	Rev	

**Hockley & Dawson**  
Consulting Engineers

Hockley & Dawson Consulting Engineers Limited  
5 Birtley Courtyard  
Bramley  
Surrey  
GU5 0LA

Telephone 01483 548784  
admin@hockleyanddawson.co.uk  
www.hockleyanddawson.co.uk