

Item	Description	Unit	Measure	Price	Cost (£)
1	Drainage of cemetery extension area				
1.1 - 1.8	Transport and preliminaries	Item			
2	Outfall				
2.1	Install headwalls as specified in ditch	No.	2		
2.1	Excavation under path by hand avoiding services, installing pipe and making good again	Item	1		
	Installation of drains				
3.1	Supply and install 80 mm lateral drains including backfill at 500 mm depth at 9 m centres	Lin m	189		
3.2	Supply and install 150 mm collector drain including backfill at 600 mm depth	Lin m	64		
3.3	Supply and install 100 mm carrier drain including backfill	Lin m	48		
3.1-3.3	Supply and install proprietary junctions	No.	9		
3.4	Supply and install roadside drains	Lin m	60		
3.5	Supply and install pre-cast concrete inspection chamber	No.	1		
4	Reinstatement of drain runs				
4.1	Topping up drain runs	Lin m	253		
4.2	Seeding drain runs	Lin m	361		
4.3	Hedge tree replacement (provisional item)	Item	1		
5	Establishment of detention basin and installation of hydrobrake				
5.1	Total herbicide application	m ²	55		
5.1	Flail mowing, dispose on site	m ²	55		
5.1	Topsoil strip (top 250 mm)	m ³	14		
5.1	Subsoil excavation and disposal on site in shaped bund	m ³	27.5		
5.1	Subsoil rip and grade	m ²	55		
5.1	Topsoil placement	m ³	14		
5.1	Topsoil box grade	m ²	55		
5.1	Supply and spread pre-seeding fertiliser	m ²	55		
5.1	Supply and drill grass seed	m ²	55		
5.1	Roll with Cambridge roller	m ²	55		
5.2	Supply and install hydrobrake chamber	No.	1		
6	Completion and provision of as-built drawings	Item	1		
		Sub total			£0.00
		10% contingency			£0.00
		Total cost of contract			£0.00