



## CRANLEIGH PARISH COUNCIL

### Specification for Snoxhall Fields Adult Pitch Improvements May 2020

#### Project Brief

To upgrade the adult football pitch at Snoxhall Fields to meet the requirements of the Football Association Ground Grading requirements for category H grounds:

<http://www.thefa.com/-/media/thefacom-new/files/about-the-fa/2019/ground-grading/grade-h-july-2019.ashx?la=en>

#### Project Timescale

13 May 2020	Invitation to tender advertised on Contracts Finder
06 July 2020	Tender closes at 9.00am
16 July 2020	Parish Council meeting to select contractor
August 2020	Works commencement
September 2020	Works completion

#### Procurement Type

Open procedure

#### Budget

£65,000

#### Specification

Please refer to scale drawing accompanying this document.

##### 1. Pitch

Include marking out pitch in new location and larger size as per drawing.

##### 2. Spectator Rail Fencing

- Supply and install 1.2m high spectator rail fencing, 2.525 post centres, 60.3mm diameter rail, 60 x 60mm posts.
- Mesh with single 5mm vertical wires at 50mm centres and dual 6mm horizontal wires at 200mm centres.
- Materials are galvanised and polyester powder coated.
- Pedestrian gates x 6 1.2m wide
- Vehicle access gates double leaf 4m wide
- Colour: green
- Complaint to FA safety guidelines
- Removal of existing metal fencing and gates

##### 3. Walkway Around the Pitch

- Dispose of existing concrete path
- Width 1.2m
- Weed protection membrane
- Base: 100mm type 1 stone
- Surface: tarmac
- Edging: concrete edging set
- Walkway set behind spectator rail.

#### **4. Dugouts**

- Remove and dispose of breeze block dugouts, level site, return to grass.
- Supply and install two dugouts size 5m on the eastern boundary with a minimum of 3m between dugouts, spaced evenly 3m from pitch centre line.
- Front of dugouts in line with the spectator rail.
- Premier Standard Steel Team Shelter
- Depth 1.3m and full head height 2.07m
- Made from 50mm steel throughout
- Bolting down plates
- Treated wood slatted seating
- 4mm shatter proof clear Makrolon sheeting to top half
- 3mm thick steel sheeting anti-vandal for bottom half
- Colour: powder coated green

#### **5. Goal Posts**

- Supply and install aluminium socketed goal posts set in concrete with back support brace for box nets and standard nets

#### **6. Floodlights**

- Upgrade six existing stanchions to LED floodlights.
- Upgrade switch timer to include auto-shut off

#### **7. Storage Container Location**

- Level ground opposite Snoxhall Pavilion machine shed and provide a level base.
- Crane lift storage container to new location.

#### **Information to be included with your quotation:**

1. Confirmation that you will provide your staff with all necessary personal protective equipment.
2. Removal of all waste from site.
3. Provision of site compound on site surrounded by HERAS fencing.
4. Compliance with CDM Regulations.
5. Copy of your public and employer liability insurance.
6. Copy of your relevant qualifications.
7. Details of your membership of professional organisations.
8. Details of a reference.
9. Copy of testimonials.
10. Please detail any areas that you feel the Parish Council may have overlooked in this invitation to quote.

The Council will consider the appointment of a contractor at its meeting on Thursday 18 July 2020.

Please submit your quotation and copies of further information required Cranleigh Parish Council **by 9.00am on Monday 06 July 2020.**